

SITE AREA

Total Site Area as per DP Approved	29,744.37 Sqm.
Kharab Land	1,718.89 Sqm.
Net Site Area	28,024.48 Sqm.
Net Site Area Excluding Kharab	28,024.48 Sqm.
Deduct 5% area of net Site Area	1,414.88 Sqm.
Net Site Area Considered for Development	26,609.60 Sqm.

AREA STATEMENT BLOCK-1, WING - A & B

FLOORS	BUA	DEDUCT	NET	UNITS
GROUND FLOOR	5,325.73	4,313.06	1,012.67	0
FIRST FLOOR	3,062.40	61.11	3,001.29	17
SECOND FLOOR	3,168.91	61.11	3,097.80	19
THIRD FLOOR	3,262.45	162.99	3,099.46	19
FOURTH FLOOR	3,162.99	61.11	3,101.88	19
FIFTH FLOOR	3,162.16	61.11	3,101.05	19
SIXTH FLOOR	3,161.59	61.11	3,100.48	19
SEVENTH FLOOR	3,161.20	61.11	3,100.09	19
EIGTH FLOOR	3,161.11	61.11	3,100.00	19
NINETH FLOOR	3,131.04	61.11	3,069.93	19
TENTH FLOOR	3,002.15	61.11	2,941.04	18
ELEVENTH FLOOR	2,774.16	61.11	2,713.04	16
TWELVETH FLOOR	2,281.55	61.11	2,220.44	12
THIRTEENTH FLOOR	1,473.69	39.33	1,434.31	7
FOURTEENTH FLOOR	1,063.30	30.56	1,032.74	5
TERRACE FLOOR	168.02	168.02	-	-
TOTAL	44,492.44	5,376.22	39,116.22	227

AREA STATEMENT BLOCK - 2, WING - C

FLOORS	BUA	DEDUCT	NET	UNITS
GROUND FLOOR	1,971.85	1,865.05	106.80	0
FIRST FLOOR	1,971.85	1,830.30	141.55	0
SECOND FLOOR	1,091.85	13.55	1,078.30	6
THIRD FLOOR	1,094.62	13.55	1,081.07	6
FOURTH FLOOR	1,068.22	13.55	1,054.67	6
FIFTH FLOOR	1,097.19	13.55	1,083.64	6
SIXTH FLOOR	1,105.78	13.55	1,092.23	6
SEVENTH FLOOR	1,116.03	13.55	1,102.53	6
EIGTH FLOOR	1,092.57	13.55	1,079.02	6
NINETH FLOOR	997.20	13.55	983.65	5
TENTH FLOOR	936.77	13.55	923.22	5
ELEVENTH FLOOR	636.92	13.55	623.37	3
TWELVETH FLOOR	535.26	13.55	521.71	3
THIRTEENTH FLOOR	432.86	8.53	424.13	2
FOURTEENTH FLOOR	172.86	4.10	168.46	1
TERRACE FLOOR	61.57	61.57	-	-
TOTAL	15,413.26	5,818.90	11,494.35	61

AREA STATEMENT BLOCK - 1, WING - D, CLUB HOUSE

FLOORS	BUA	DEDUCT	NET
GROUND FLOOR	1,516.60	1,146.05	370.55
FIRST FLOOR	948.06	7.49	940.60
SECOND FLOOR	510.28	7.49	502.79
THIRD FLOOR	530.11	33.88	496.13
FOURTH FLOOR	288.49	7.49	279.00
TERRACE FLOOR	40.81	40.81	-
TOTAL	3,834.48	1,245.41	2,588.07

COMBINED AREA STATEMENT

FLOORS	BUA	DEDUCT	NET	UNITS
GROUND FLOOR	8,816.18	7,326.16	1,490.02	0
FIRST FLOOR	5,982.34	1,898.90	4,083.44	17
SECOND FLOOR	4,761.04	82.15	4,678.89	25
THIRD FLOOR	4,887.18	210.52	4,676.66	25
FOURTH FLOOR	4,547.70	82.15	4,465.55	25
FIFTH FLOOR	4,295.35	74.66	4,184.69	25
SIXTH FLOOR	4,267.37	74.66	4,192.71	25
SEVENTH FLOOR	4,277.23	74.66	4,202.57	25
EIGTH FLOOR	4,253.68	74.66	4,179.02	25
NINETH FLOOR	4,128.24	74.66	4,053.58	24
TENTH FLOOR	3,938.92	74.66	3,864.26	23
ELEVENTH FLOOR	3,411.07	74.66	3,336.41	19
TWELVETH FLOOR	2,816.81	74.66	2,742.15	15
THIRTEENTH FLOOR	1,906.65	48.21	1,858.44	9
FOURTEENTH FLOOR	1,225.86	34.66	1,191.20	6
TERRACE FLOOR	260.50	260.50	-	-
TOTAL	63,740.17	10,640.53	53,199.64	286

COVERAGE = 8,816.18 / 23,576.76 x 100 = 36.92% < 60.00%

FAR = 53,199.64 / 28,609.60 = 1.99 < 2.00

PARKING :

Residential:

Total Nos. of Residential Units from GF to 14th Floor in Block A, B & C = 286 Nos.
@ 1 car / unit, Cars Required = 286 x 1 = 286 cars
No of EWS's Provided = 29 Nos.
@ 1 car / 2 unit, Cars Required = 29/2 = 14.50 say 15 cars
Total Cars Required for Residential Units = 286 + 15 = 303 Cars
10% Visitors Parking = 303 / 10 = 30.30 say 31 cars

Club House Area

Total FAR Area From GF to 4th Floor = 2,588.07 Sqm.
@ 1 Car / 50 Sqm, Cars Required = 2,588.07 / 50 = 51.76 Say 52 Cars

Total Cars Reuired = 303 + 31 + 52 = 386 Cars

Total Cars Provided

Ground Floor Resi.Block A & B	=	100 cars
Ground Floor Resi.Block C	=	36 cars
First Floor Resi.Block C	=	30 cars
Ground Floor Club House	=	42 cars
Surface Parking	=	180 cars
Total	=	388 cars

E.W.S. CALCULATION:

E.W.S. UNITS REQUIRED	10% OF TOTAL 286 UNITS= 29 UNITS	
	E.W.S. UNIT	No.
	UNIT - W	14
	UNIT - R	10
	UNIT - N	01
	UNIT - K	01
	UNIT - U	01
	UNIT - P	01
	UNIT - Q	01
E.W.S. UNITS PROVIDED	TOTAL	29

BBMP/Addl.Dir/ JD NORTH/ 0515/2013-14

Conditions:

1. Sanction is accorded for the proposed construction of Residential Apartment Building.
2. Construction of Block - 1, Wing - A & B, GF+14 UF Wing D, Club House- GF+4 UF, Block - 2, Wing - C, GF+14 UF
3. Sanction is accorded for Residential use only. The use of the building shall not be deviated to any other use.
4. Ground Floor and Part of First Floor area reserved for car parking shall not be converted for any other purpose.
5. Development charges towards increasing the capacity of water supply, sanitary and power mains has to be paid to BWSSB and BESCOM if any.
6. Necessary clubs for running telephone cables, cubicles at ground level for postal services & space for dumping garbage within the premises shall be provided.
7. The applicant shall construct temporary toilets for the use of construction workers and it should be demolished after the completion of work.
8. The applicant shall INSURE all workmen involved in the construction work against any accident / untoward incidents arising during the time of construction.
9. The applicant shall not stack any building materials / debris on footpath or on roads or on drains. The debris shall be removed and transported to near by dumping yard.
10. The applicant / builder is prohibited from selling the setback area / open spaces and the common facility areas, which shall be accessible to all the tenants and occupants.
11. The applicant shall provide a space for locating the distribution transformers & associated equipment as per K.E.R.C (Ele & D) code leaving 3.00 mts. from the building within the premises.
12. The applicant shall provide a separate room preferably 4.50 x 3.65 m in the basement for installation of telecom equipment and also to make provisions for telecom services as per Bye-law No. 28.
13. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other hazards endangering the safety of people / structures etc. in & around the site.
14. The applicant shall plant at least two trees in the premises.
15. The applicant shall obtained from forest department for cutting trees before the commencement of the work.
16. License and approved plans shall be posted in a conspicuous place of the licensed premises. The building license and the copies of sanctioned plans with specifications shall be mounted on a frame and displayed and they shall be made available during inspections.
17. If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be informed by this Authority in the first instance, warned in the second instance and cancel the registration if the same is repeated for the third time.
18. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule – IV (Bye-law No. 3.6) under sub section IV-B (a) to (k).
19. The building shall be constructed under the supervision of a registered structural engineer.
20. On completion of foundation or footings before erection of walls on the foundation and in the case of reinforced structure before erecting the columns "FOUNDATION CERTIFICATE" shall be obtained.
21. Construction or reconstruction of the building should be completed before the expiry of five years from the date of issue of the license and the application should be submitted for permission to occupy the building.
22. The building should not be occupied without obtaining the "OCCUPANCY CERTIFICATE" from the competent authority.
23. Drinking water supplied by BWSSB should not be used for the construction activity of the building.
24. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non potable purposes or recharge of ground water at all times having a minimum capacity mentioned in the Bye-law 32(a)
24. The building shall be designed and constructed adopting the norms prescribed in National Building Code and in the "Criteria for earthquake resistant design of structures" bearing No. IS 1893-2002 published by the Bureau of Indian Standards for making the building resistant to earthquakes.
25. The applicant should provide solar water heaters as per table 17 of Bye-law No. 29 for the building.
26. Facilities for physically handicapped persons prescribed in schedule XI of Bye – Laws 2003 shall be ensured.
27. The applicant shall provide at least one common toilet for the ground floor for the use of the visitors, servants / drivers and security guard and also ensure shall be approached through a ramp for the Physically Handicapped persons and equipped with the railings etc.
28. The Occupancy Certificate will be considered only after ensuring that the provisions of conditions as Sl.No. 23, 24, 25 & 26 are provided in the building.
29. The applicant shall ensure that no inconvenience is caused to the neighbours in the vicinity of construction and the construction activities shall also before 10.00 pm to avoid hindrance during late hours.
30. Garbage originating from Apartments / Commercial buildings shall be segregated into organic and inorganic waste and should be processed in the Recycling processing unit (10 kg. capacity installed as use for treating organic waste) if applicable for Residential units of 50 and above and 5000 Sqm and above built up area for Commercial building).
31. The structures with basements shall be designed for structural stability and safety to ensure for soil investigation during the course of excavation for basements with safe design for retaining walls and super structure for the safety of the structure as well as neighbouring property, public roads and footpaths, and besides ensuring safety of workmen and general public by erecting safe barricades.
32. Adequate rain water marking shall be provided as per requirement.
33. Traffic Management Plan shall be obtained from Traffic Management Consultant for all high rise structures which shall be got approved from the Competent Authority if necessary.
34. The owner / Association of high rise building shall obtain electrical certificate from Fire Force Department once every Two years with due inspection by the department regarding working condition of Fire Safety measures installed. The certificate should be produced to the corporation and shall get the renewal of the permission issued once in Two years.
35. The Owner / Association of the highrise building shall get the building inspected by empanelled agencies of the Fire Force Department to ensure that the fire equipments installed are in good and workable condition, and an affidavit to that effect shall be submitted to the corporation and Fire Force Department every year.
36. The owner / Association of highrise building shall obtain clearance certificate from the Electrical Inspectorate every Two years with due inspection by the department regarding working condition of Electrical installations / Lifts etc. The certificate should be produced to the corporation and shall get the renewal of the permission issued once in Two years.
37. The Owner / Association of the highrise building shall conduct two mock – drills in the building, one before the onset of summer and another during the summer and assure complete safety in respect of fire hazards.
38. Payment of license fees for sanction of this plan is subject to result of W.P.No. 4906/2008 & 29932/2008.
39. Payment of taxes to the property should be paid as decided by the BBMP in future.
40. All other conditions laid down by Bangalore Development Authority while approving the Development Plan for the project should be strictly adhered to.
41. In case of any false information, misrepresentation of facts, or pending court cases, the plan sanctioned / deemed sanctioned, shall stand cancelled.
42. The Modified NOC from Fire & Emergency Services Department should be submitted before obtaining Occupancy Certificate / Commencement of Work.

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM (Hosadaagi Hoodike) Letter No: LD/95/LET/2013, dated: 01-04-2013

1. Registration of Applicant / Builder / Owner / Contractor and the construction workers working in the construction site with the Karnataka Building and Other Construction workers Welfare Board should be strictly adhered to.
2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers working in the site to the Commencement Certificate. A copy of the same shall also be submitted to the concerned Asst Engineer in order to inspect the establishment and ensure the registration of establishment and workers working at construction site or work place.
3. The Applicant / Builder / Owner / Contractor shall also inform the changes if any of the list of workers engaged by him.
4. At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in his site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board"

Note:

1. Accommodation shall be provided for setting up of schools for imparting education to the children of construction workers in the labour camps / construction sites.
2. List of children of workers shall be furnished by the builder / contractor to the Labour Department which is mandatory.
3. Employment of child labour in the construction activities strictly prohibited.
4. Obtaining NOC from the Labour Department before commencing the construction work is a must.
5. BBMP will not be responsible for any disputes that may arise in respect of property in question.
6. In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned / deemed sanctioned shall stand cancelled automatically and legal action will be initiated.

ii. NOC Details :

Sl. No.	Name of the Statutory Department	Reference No. & Date	Conditions imposed
1	Fire Force Department	DBD/1(119)/2013, dated: 05-10-2013	The condition imposed in the letter issued by the Statutory Authority shall be adhered to.
2	HAL	AAI/BIA/ATM/NOC/BANG-SOUTH/ 81/09031/3/15641/1009-09, dated: 04-09-2013	
3	BIAL	/BIAL/GC/CON/2013/ dated: 30-09-2013	
4	KFCS	FCS/1(2)/CFO/13/47783, dated: 06-07-2013	
5	BWSSB	BWSSB:EIC/ACE(M)-HOC(M)-IT(AM) /43472/2013-14, dated: 10-07-2013	
6	BESCOM	SEE/BCS/EE(O)/AE2.2/NOC-05/13-14/4158-60, dated: 13-06-2013	

iii. The Applicant has paid the fees vide Receipt No.TPJ/DTP/NRT/01/2014-15/Bapj/0055 dtd: 20-05-2014 for the following:-

1	Licence Fees	52,04,170-00
2	Ground Rent	25,49,607-00
3	Betterment Charges	
	a) For Building	1,27,480-00
4	Layout Deposit	63,74,017-00
5	Plan Scrutiny Fee	1,72,000-00
6	Component Wise Charges	10,000-00
7	1% Service Charge on Labour Cess to be paid to BBMP	68,610-00
	TOTAL :	1,45,86,883-00
	SAY Rs.	1,45,86,880-00
8	Labour Cess	67,52,500/- Paid vide DD No. 077381 dated : 16-2014

ಸಕಲು ಪ್ರತಿ

ಸಹಾಯಕ ನಿರ್ದೇಶಕರು (ನಗರ ಯೋಜನೆ) ಉತ್ತರ ವಿಭಾಗ, ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

AREA STATEMENT- OVERALL AREA STATEMENT

SL.NO	SY.NO.	SY.NO. ACRES -GTS
01	71	1A-17 GTS
02	89	1A-00 GTS
03	90	3A-30 GTS
04	91/1	0 A-09 GTS
05	91/2	0 A-09 GTS
06	94/1	0 A-22 GTS
07	94/3	0 A-07 GTS
		7A - 14 GTS

AREA OF PLOT (A)		= 29744.37 SQM (7 acres 14 guntas)
	kharab land (x)	= 1718.89 SQM (0 acres 37 guntas)
TOTAL AREA OF PLOT EXCLUDING (kharab)		= 28024.48 SQM. (6 acres 37 guntas)
	RMP ROADAREA	= 2734.14 SQM.
AREA OF PLOT(B) excluding kharab land	(A) - (X)	= 28,024.48 SQM. (6 acres 37 guntas)
PERMISSIBLE F.A.R		= 2.00
F.A.R Achieved		= 1.99
10% of park & open space of (B)		= 2,802.46 SQM. (C)
5% of civic amenities of (B)		= 1,401.23 SQM. (C)
Total site available for development(E) =		= 28,024.48 -1414.58 = (E) = 26,609.90 SQM.
PERMISSIBLE F.A.R AREA		= 53219.80 SQM.
F.A.R AREA ACHIEVED		= 53199.64 SQ.M.
F.A.R ACHIEVED		= 1.99
PERMISSIBLE GROUND COVERAGE		= 60%
PROPOSED GROUND COVERAGE AREA		= 9064.99 SQ.M.
PROPOSED GROUND COVERAGE		= 8,816.18 SQ.M / 23,576.76 SQ.M. x 100 = 36.92%

CIVIC AMENITIES

S.No	DESCRIPTION	AREA in Sqm
01.	PROPOSED CIVIC AMENITIES	1414.58
	PROPOSED PERCENTAGE ACHIEVED	5.04%

PARK & OPEN SPACE STATEMENT

02.	PROPOSE AREA (POS-1)	3123.73
	PROPOSE PERCENTAGE ACHIEVED	11.14%

KHARAB LAND
RWHP rain water harvesting pit
TERRACE AT FIRST FLOOR LVL
OPEN SPACE
nala buffer as per dp
PARKING
15 m nala buffer line
BOUNDARY LINE
SETBACK LINE

NOTE:
01.ALL DIMENSIONS IN METERS ONLY
02.FOLLOW THE WRITTEN DIMENSIONS

SANCTION PLAN DRAWING

JOB TITLE:
PROPOSED RESIDENTIAL APARTMENT PLAN FOR BBMP :KHATA NO 1208/1409/1385/71,89,90 WARD NO 150, SURVEY NO.71,89 ,90 ,91/1 ,91/2, 94/1 ,94/3 HARALUR VILLAGE, VARTHUR HOBLI, BANGALORE EAST TALUK.

Scale	Drawn	sheet no
1:400	ashish	01/20
	Chkd	
	tushar	

NORTH

OWNER'S SIGNATURE

FERNS BUILDER'S & DEVELOPER'S & AUSTIN ROACH

ARCHITECT'S SIGNATURE

TUSHAR.V (BCC/BL-3.6/A-1730/07-08)

Site Plan

sanction drawing

DRG.NO:rbrr.w.a.a.wd_plan-development-04

COPYRIGHTS RESERVED