

AREA STATEMENT

SITE AREA	= 89,688.46 SQM = 22 acres, 6.5 guntas
KHARAB LAND	= 1,315.23 SQM = 13 guntas
SITE AREA (AFTER DEDUCYING KHARAB LAND)	= 88,373.23 SQM = 21 acres, 33.5 guntas
AREA TO BE RESERVED FOR CIVIC AMENITIES @ 5% OF PLOT AREA	= 4,418.66 SQM
AREA PROVIDED FOR CIVIC AMENITIES	
CA-1	= 2059.08
CA-2	2358.28
TOTAL	4417.66
	= 5.00 %
NET PLOT AREA AVAILABLE FOR DEVELOPMENT	= 89,688.46 - 4418.66 = 83,954.57SQM
PARK & OPEN SPACES TO BE RESERVED @ 10% OF PLOT AREA	= 8,837.32 SQM = 95,124.12 SQ FT
PARK & OPEN SPACES PROVIDED	= 8,901.92 SQM = 10.07 %
SITE AREA CONSIDERED FOR FAR CALCULATION (95% OF NET SITE AREA AFTER DEDUCTION OF KHARAB LAND)	= 83,954.57 SQM
PERMISSIBLE F.A.R	= 2.5
ACHIEVED F.A.R = 2,09,685.45 / 83,954.57	= 2.497
PERMISSIBLE F.A.R AREA	= 2,09,886.42 SQM.
ACHIEVED F.A.R AREA	= 2,09,685.45 SQM.
AREA LEFT FOR ROAD WIDENING = (RW-01 + RW-02) = 1874.33 + 549.90 =	= 2,224.23 SQM.
PERMISSIBLE GROUND COVERAGE	= 55 %
ACHIEVED GROUND COVERAGE	= 16.02 %
PERMISSIBLE GROUND COVERAGE AREA	= 47,381.95 SQM.
ACHIEVED GROUND COVERAGE AREA	= 15,801.33 SQM.
HEIGHT OF THE BUILDING TOP OF OVERHEAD TANK = 64.65m TOP OF TERRACE FLOOR SLAB = 59.65m	
SETBACKS MINIMUM SETBACK REQUIRED = 16.00 M MINIMUM SETBACK PROVIDED = 17.00 M	
TOTAL ACHIEVED F.A.R AREA	= 2,09,685.45 SQm
BALANCE F.A.R AREA	= 200.97 SQm
ACHIEVED F.A.R = TOTAL F.A.R AREA / SITE AREA = 2,09,685.45 / 83,954.57	= 2.497
ACHIEVED F.A.R	= 2.497

GROUND COVERAGE STATEMENT

AREA OF PLOT = AFTER DEDUCTION OF KHARAB LAND & ROAD WIDENING = 89,688.46 - (1,315.23 + 2,224.23)	= 86,149.01 SQM
PERMISSIBLE GROUND COVERAGE	= 55%
PERMISSIBLE COVERAGE AREA	= 47,381.95 SQm
ACHIEVED GROUND COVERAGE AREA	= 13,801.33 SQm.
ACHIEVED COVERAGE = COVERAGE AREA / SITE AREA X 100 = 13,801.33 / 86,149.01 X 100	
ACHIEVED GROUND COVERAGE	= 16.02 %

PARKING STATEMENT

PARKING REQUIRED FOR RESIDENTIAL BUILDING
TOTAL NUMBER OF CAR-PARKS REQUIRED AT THE RATE OF
1 CAR PARK PER DWELLING UNITS ABOVE 50 SQM TO 150 SQM ADDITIONAL
1 CAR PARK FOR PART THEREOF, WHEN IT IS MORE THAN 50%
OF THE PRESCRIBED UNIT FOR ADDITIONAL FOR VISITORS

TOTAL NUMBER OF UNITS PROPOSED :	= 1632 units
NO OF CARPARKS REQUIRED	= 1632 Nos
10% VISITORS PARKING	= 163 Nos
CLUB HOUSE: = 50sqm / CAR = 3250 / 50	= 65 Nos
TOTAL CAR PARKS REQUIRED:	= 1,860 Nos

PARKING PROVIDED :

SLNO.	CAR-PARKS	NUMBERS
1	BASEMENT FLOOR	950
2	STILT FLOOR	852
3	SURFACE	163

TOTAL PARKING PROVIDED: 1,965 nos

UNIT CALCULATION

UNIT TYPE	TYPE - A	TYPE - B	TYPE - C	TYPE - D	TYPE - E	TYPE - F	TYPE - G	TOWER - WISE TOTAL
	1 BED	1 BED	1 BED	2 BED	2 BED	2.5 BED	3 BED	
TOWER NO	46.52 sqm	50.60 sqm	53.87 sqm	98.41 sqm	100.81 sqm	105.35 sqm	131.85 sqm	
	UNIT Nos.	UNIT Nos.	UNIT Nos.	UNIT Nos.	UNIT Nos.	UNIT Nos.	UNIT Nos.	
01	0	0	4	4	56	32	32	128
02	0	0	4	8	56	32	32	128
03	64	64	4	12	112	0	0	256
04	0	0	4	4	56	32	32	128
05	0	0	4	4	56	32	32	128
06	0	0	8	8	126	72	72	288
07	0	0	8	8	112	64	64	256
08	0	0	8	8	112	64	64	256
09	0	0	4	4	56	32	32	128
TOTAL	64	64	48	56	744	360	360	
TOTAL NUMBER OF UNITS =								1696.00

PLAN OF RECHARGE PIT

TYPICAL RAIN WATER RECHARGE PIT

MS Ramaiah North East county
BMS Institute of Technology
CRPF Campus Yelahanka
Kendriya Vidyalaya CRPF
PRESTIGE MONTE CARLO
RAMANASHREE CALIFORNIA RESORT
Yelahanka Satellite Town
SITE
nagenahalli (village)
CRPF Hospital / Quarters
Heritage Estate
To Kempegowda International Airport
To BANGALORE CITY Kodigehalli Flyover Approx 11Km from SITE)

A LOCATION PLAN
SCALE - 1 NTS

N

B SURVEY PLAN
SCALE - 1 NTS

STATEMENT FOR PARK & OPEN SPACES
REQ 10% OF = 8837.32 SQM

PART NO	AREA IN m²
PART - P1	8589.91
PART - P2	312.13
TOTAL SQM	8901.92
TOTAL PROVIDED	10.07%

STATEMENT FOR CIVIC AMENITIES
REQ 5% OF = 4418.66 SQM

PART NO	AREA IN SQM
CA-1	2059.08
CA-2	2358.28
TOTAL SQM	4417.66

FLOOR	BUILT UP AREA in m² GROSS	DEDUCTION SHAFT	CUT OUT	BUILT UP AREA	FAR DEDUCTION LFT	TERRACE	FAR AREA
	G	S	C	B=G-(S+C)	L	R	F=B-(L+R)
SUB TOTAL	230852.18	6987.39	16865.59	205999.20	3968.64	1358.15	201672.41

BASEMENTS & STILT
FAR AREA CALCULATION

FLOOR	BUILT UP AREA in m² GROSS	DEDUCTION SHAFT	CUT OUT	BUILT UP AREA	FAR DEDUCTION LFT	PARK	FAR AREA
	G	S	C	B=G-(S+C)	L	P	F=B-(L+P)
BASEMENT FLOOR	44166.66	4.1	0.0	44162.56	243.36	40917.30	3001.90
SUB TOTAL	88310.00	83.37	666.75	87560.88	243.36	82964.48	4763.04
CLUB HOUSE	3250			3250			3250

KEY PLAN

NOTES
ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE SPECIFIED

LEGEND
TOWER BLOCKS
ROAD WIDENING AREA HANDED OVER TO AUTHORITY
PARK & OPEN SPACES CONSIDERED
CIVIC AMENITIES
9M WIDE FIRE DRIVE
LANDSCAPED AREA ON MOTHER EARTH
LANDSCAPED AREA ON PODIUM
SITE BOUNDARY LINE
16M SETBACK LINE
BASEMENT EXTENSION LINE
BUILDING LINE
10m SET BACK FROM RAILWAY LINE

CLIENT
PRESTIGE GROUP

OWNERS SIGNATURE
GPA HOLDER

ARCHITECTS SIGNATURE
TILAK THOMAS
(B.C.C/B L/3.2.3/A-972/2001-2002)

PROJECT TITLE
RESIDENTIAL BUILDING ON SY.NO-11,12,13/1,13/2,13/3,16/2,17,18,19/1A, 19/1B,19/2,20,21,22/1,22/2,23/1,23/2,23/3, 24,25,~~26/1A,26/2B,26/2C,26/3,26/4,~~ 26/5A,~~26/5B,~~ ~~28/1,29/2,~~28/3,29,30,31, 32/1,32/2,45,~~46/1,46/2B,~~SITUATED @ AVALAHALLI VILLAGE,YELAHANKA HOBLI, DODDABALAPUR ROAD, BANGALORE.

DRAWING TITLE: DEVELOPMENT PLAN
SHEET NO: of 1
DWG NO: AS-101
DATE: 12-09-2013

	NAME	SCALE	ORIENTATION
CHKD	BA	1:600	N
DEALT	BA		
DRAWN	ANR		

DEVELOPMENT PLAN

ARCHITECTS:
THOMAS ASSOCIATES ARCHITECTS

CONDITIONS:
1. The Approved Development Plan is approved vide Authority Resolution