

Office of the Director General of Police
 Commandant General, Home Guards &
 Director of Civil Defence and
 Director General Karnataka State Fire &
 Emergency Services
 No. 1, Annaswamy Mudaliar Road
 Bangalore - 560 042



Phone : 25570733
 : 22971501
 Fax : 22971512

No.GBC(1)190/2011

17-02-2014

To
 The Commissioner,
 Bruhath Bangalore Mahanagara Palike,
 N.R. Square,
 Bangalore -560002.

Sir,

Sub: Issue of Revised No Objection Certificate for the construction
 of High Rise Residential Building i.e. Tower-2 at Property No.
 1D No. 14-1-1, No.1, Industrial Suburb, Ward No. 14, Nagapura,
 Opp. Vivekananda College, Dr. Rajkumar Road, Bangalore-reg.


Ref: 1) This office NOC No.GBC(1)281/2013 dated 25-08-2011.
 2) This office revised NOC No.GBC(1)281/2013 dated 22-06-2013
 issued for Tower-1 & Tower-3.
 3) Letter dated 31-05-2013 of the Authorized Signatory,
 M/s.Palladium Constructions Pvt. Ltd., M/s.Palladium Spaces
 Pvt. Ltd., No.1, Industrial Suburb, Ward No.14, Nagapura,
 Opp.Vivekananda College, Dr.Rajkumar Road, Bangalore
 - 560 010.

AAAAA


In the reference, cited at (1) above, NOC for the construction of High Rise Residential Buildings with 3 Towers i.e. Tower-1 with 2 blocks i.e. Block-1 with ground and 18 upper floors & Block-1a with 2 basements, ground and 18 upper floors joined together with a club house between 2 Blocks. Tower-2 with 2 basements, ground and 25 upper floors and Tower-3 with 5 Blocks i.e. Block-3, 3a & 3b, each with 3 common basements, ground and 30 upper floors & Block 3c & 3d, each with basement, ground and 20 upper floors joined together with a club house between Block-3b & 3c i.e. Tower-2 comprising of 4 Basements, Ground & 31 upper floors at Property No.1D No.14-1-1, No.1, Industrial Suburb, Ward No.14, Nagapura, Opp. Vivekananda College, Dr. Rajkumar Road, Bangalore was issued. In the reference, cited at (2) above revised NOC has been issued for 2 towers i.e. Tower-1 & Tower-3 building. Now the applicant, in his letter, cited at (3) above, has informed about change in the plan in Tower-2 also and requested to issue a revised NOC. Accordingly the Chief Fire Officer, Bangalore West Zone of this department has re-inspected the site of proposed High Rise Residential Building i.e. Tower-2 at Property No. 1D No. 14-1-1, No.1, Industrial Suburb, Ward No. 14, Nagapura, Opp. Vivekananda College, Dr. Rajkumar Road, Bangalore on 11-11-2013 with reference to the revised drawings, submitted by the applicant and has furnished the details as follows :-

A. Details of the premises.

1. Address of the premises : Property No. 1D No. 14-1-1,
No.1, Industrial Suburb,
Ward No. 14, Nagapura,
Opp. Vivekananda College,
Dr. Rajkumar Road,
Bangalore.
2. Number of Building : One Building i.e. Tower-2.
3. Number of floors : 4 Basements, ground & 31 upper floors.
4. Type of Occupancy : Residential.
5. Floor wise details of the Occupancy :-
 - Basement – 4 : For parking 240 Cars.
 - Basement – 3 : For parking 210 Cars, 1 Panel Room and 1 Pump & Plant Room.
 - Basement – 2 : For parking 208 Cars & 1 Panel Room.
 - Basement – 1 : For parking 191 Cars, 1 D.G. Room & 3 Communication Room.
 - Ground floor : 1 Reception, 1 Multipurpose Hall, 1 Kitchen, 1 Pantry, 1 Café, 1 Business Centre Areas, 1 Billiards/Cards Room, 1 Mini Theatre, 1 TT Room, 1 Kids Games Room, 1 Creche, 1 Storage, 1 Squash Room, 1 Change Room & 4 Electrical Room.
 - 1st floor : 5 flats.
 - 2nd floor : 5 flats, out of which 1 flat is duplex type.
 - 3rd floor : 4 flats.
 - 4th floor : 5 flats, out of which 1 flat is duplex type.
 - 5th floor : 4 flats.
 - 6th floor : 5 flats, out of which 1 flat is duplex type.
 - 7th floor : 4 flats.



8 th floor	:	5 flats, out of which 1 flat is duplex type.
9 th floor	:	4 flats.
10 th floor	:	5 flats, out of which 1 flat is duplex type.
11 th floor	:	4 flats.
12 th floor	:	5 flats, out of which 1 flat is duplex type.
13 th floor	:	4 flats.
14 th floor	:	5 flats, out of which 1 flat is duplex type.
15 th floor	:	4 flats.
16 th floor	:	5 flats, out of which 1 flat is duplex type.
17 th floor	:	4 flats.
18 th floor	:	5 flats, out of which 1 flat is duplex type.
19 th floor	:	4 flats.
20 th floor	:	5 flats, out of which 1 flat is duplex type.
21 st floor	:	4 flats.
22 nd floor	:	5 flats, out of which 1 flat is duplex type.
23 rd floor	:	4 flats.
24 th floor	:	5 flats, out of which 1 flat is duplex type.
25 th floor	:	4 flats.
26 th floor	:	5 flats, out of which 1 flat is duplex type.
27 th floor	:	4 flats.




28 th floor	:	5 flats, out of which 1 flat is duplex type.
29 th floor	:	4 flats.
30 th floor	:	5 flats.
31 st floor	:	2 Lounge, 1 Pantry, 1 Aerobics, 2 Spa, 1 Swimming Pool, 1 Fitness Centre & 1 Weight Room.

Total : 136 flats.

8. Height of the Building	:	108.00 mtrs.
9. Site Area	:	67,488.073 Sq. mtrs.

10. Built-up area of each floor :-


Basement – 4	:	9,771.72 Sq. mtrs.
Basement – 3	:	9,771.72 Sq. mtrs.
Basement – 2	:	9,712.41 Sq. mtrs.
Basement – 1	:	8,939.73 Sq. mtrs.
Ground floor	:	3,244.38 Sq. mtrs.
1 st floor	:	3,577.74 Sq. mtrs.
2 nd , 6 th , 10 th , 14 th , 18 th , 22 nd , 26 th & 30 th floor (2,949.36 Sq. mtrs. on each floor x 8 floors)	:	23,594.88 Sq. mtrs.
3 rd , 5 th , 7 th , 9 th , 11 th , 13 th , 15 th , 17 th , 19 th , 21 st , 23 rd , 25 th , 27 th & 29 th (2,795.17 Sq. mtrs. on each floor x 14 floors)	:	39,132.38 Sq. mtrs.




- 4th, 8th, 12th, 16th, 20th, 24th : 20,275.99 Sq. mtrs.
& 28th floor
(2,896.57 Sq. mtrs. on each floor
x 7 floors)
- 31st floor : 3,327.22 Sq. mtrs.
11. Total Built-up area : 1,31,348.17 Sq. mtrs.
12. Surrounding properties:-
- East : 24.00 mtrs. wide Dr. Rajkumar Road.
- West : ISCON Temple.
- North : Government office Building of ground & 2 upper floors.
- South : Open land belongs to the BWSSB.

B. The plan shows the following structural details indicating the fire prevention, fire fighting and evacuation measures. These measures are considered adequate as follows:-

Details (1)	Existing (2)
1. Width of the road to which the building abuts and whether it is hard surfaced to carry the weight of 45,000 kgs.	The premises is abutting 24.00 mtrs. wide Dr. Rajkumar Road, located on the Eastern side. The Road is hardened to carry the weight of 45,000 kgs.
2. Number of entrances and width of each	Proposed to provide 2 entrances, each of 6.00 mtrs. width from 24.00 mtrs. wide Dr. Rajkumar Road, located on the Eastern side.
3. Height clearance over the entrance	No arch or any other constructions has been proposed over the entrance.




(1)	(2)
4. Width of open space (Setbacks):-	
Front (North)	: Minimum 16.00 mtrs.
Rear (South)	: Minimum 54.05 mtrs.
Side (East)	: Minimum 19.92 mtrs.
Side (West)	: Minimum 16.05 mtrs.
5. Arrangement for parking the Cars	: Provision has been made to park 240 Cars at Basement-4 parking area, 210 Cars at Basement-3 parking area, 208 Cars at Basement-2 parking area & 191 Cars at Basement-1 parking area. Proposed to provide 2 ramps for the vehicles to reach each basement parking area.
6. Number of Staircases	: 6.
7. Location of the staircases	: All the staircases have been designed to abut one of its side to the wall and are terminated at ground floor level. 7 separate staircases have been proposed to provide to reach the Basement-4 parking area from the ground floor. Further provision has been made to enclose all the staircases at each floor level.
8. Staircase size:-	
(a) Width of the staircases	: 3 each of 1.5 mtrs. & another 3 each of 1.20 mtrs.
(b) Width of treads	: 30 Cms.
(c) Height of riser	: 15 Cms.
(d) Number of risers in a flight	: Maximum 10 risers per flight.
(e) Height of hand rails	: 1.00 mtr. As proposed, the hand rails should be provided at a height of 1.00 mtr. The gap between two verticals should not exceed 15 Cms.
(f) Head room clearance	: Minimum 2.50 mtrs.



(1)	(2)
9. Travel distance from the farthest point and from dead-end of the corridor to the staircase.	Maximum 30.00 mtrs. from the farthest point to staircases in Basements. Maximum 32.00 mtrs. from the farthest point and maximum 10.00 mtrs. from the dead end of the corridor to the staircases in upper floors. Increased travel distance from the farthest point is acceptable as the entire Building is proposed to be covered with automatic sprinkler system.
10. Number of lifts and capacity.	10 passenger lifts, each of 16 passengers capacity & 3 service lifts, each of 1,600 Kgs. capacity (Total 13 lifts).

C.While constructing the building the following fire safety measures should be incorporated:-

Details (1)	Existing (2)	Recommendation (3)
1. Condition of the open space.	--	Out of the required and allowed setbacks of minimum 16.00 mtrs. around the Building, setback to an extent of 8.00 mtrs. from the Building line should have a RCC slab of 200 mm thickness to carry the load of 45,000 kgs., being the weight of a fire unit. This driveway all around the building, should always be kept free and clear. It would be advantageous to the builders and the users to elevate this portion by a few inches and even provide for a different colour, so that people are aware that this is the emergency route for fire fighting vehicles, ambulances etc. The total setbacks shall be at even level without any structure and projections up to a height of 5.00 mtrs. These setbacks shall be always kept free from any construction or utilization like garden, landscaping parking etc.



(1)	(2)	(3)
2. Structural materials.	---	RCC materials and brick walls of not less than two hours fire resistance should be used for the construction of structures. Only fire resistant materials or materials treated with fire retardant chemicals, should be used for interior decoration work. While attending the interior decoration the fixed fire fighting systems like sprinklers/risers etc., should not be covered or shifted from their original location.
3. Design of the staircases.	Not indicated	All the staircases should be constructed with non-combustible materials and should be completely enclosed at each landing to prevent smoke and fire traveling from the lower floors to the upper floors. Enclosures to staircases should be provided with self-closing smoke-stopping swing-door, fitted with door closing devices at the exit to the lobby. These doors should have at least two hours fire resistance capacity. The staircase area should be without glazing or glass brick walls to avoid reflections. Any area of dwelling or storage should not open directly to the staircase.
4. Specification of lift.	Not indicated	The brick walls, enclosing the lift shafts, should be of 90 mm thickness and have a fire resistance of not less than two hours. Shaft should have permanent vent of not less than 0.2 sq.mtrs. clear area, immediately under the machine room. Lift motor rooms should be preferably located at the top of the shaft and separated by the enclosing wall of shaft or by the floor of the machine room. Landing doors of lift enclosures should open into a ventilated lobby having one hour fire resistance. Lift car doors should be of metal finish, operating automatically and should have fire resistance capacity of one hour. Exit from the lift lobby should be through a self closing smoke stopping door of 15 mm thickness, having one hour fire resistance capacity. This is to prevent smoke and fire traveling from the lower floors to the upper floors. The lift machine rooms should be separate and no other machinery should be installed therein. Each lift should be connected to an alternative source of power (generator).



(1)	(2)	(3)
		Grounding switches at the ground floor level to enable the Fire & Emergency Services personnel to ground all the lift cars and use them as 'FIRE LIFT' in an emergency should be provided. All the lifts, extended up to the Basement-4, shall be terminated at the ground floor level or the lift lobby at the basement level shall be enclosed and pressurized with positive pressure.
5. Service ducts/shafts.	---	Service ducts should be enclosed by walls of 100 mm. thickness to have at least two hrs. fire resistance capacity. A vent, opening at the top of the service shafts, should be provided between one fourth and half of the area of the shafts. The electrical distribution cables and wiring should be laid in a separate duct. All the ducts should be sealed at every alternate floor with non-combustible metal doors having at least two hours fire resistance capacity. Water mains, telephone lines, intercom lines or any other service lines should not be laid in the duct, meant for electric cables. The inspection panel doors and any other opening to the shafts should be provided with airtight doors of at least two hours fire resistance capacity.
6. Basements Ventilation	Not indicated	Each basement shall be separately ventilated. Vents with cross-sectional area (aggregate) not less than 2.5% of the floor area spread evenly round the perimeter of the basement shall be provided in the form of grills, or breakable stall board lights or pavement lights or by way of shafts. Alternatively, a system of air inlets shall be provided at basement floor level and smoke outlets at basement ceiling level. Inlets and extracts may be terminated at ground level with stallboard or pavement lights as before, but ducts to convey fresh air to the basement floor level have to be laid. Stallboard and pavement lights should be in positions easily accessible to the fire brigade and clearly marked 'SMOKE OUTLET' or



(1)	(2)	(3)
-----	-----	-----


'AIR INLET' with an indication of area served at or near the opening. In multi-storey basements, intake ducts may serve all basement level, but each basement levels and basement compartment shall have separate smoke outlet duct or ducts. Ducts so provided shall have the same fire resistance rating as the compartment itself. Fire rating may be taken as the required smoke extraction time for smoke extraction ducts. Mechanical extractors for smoke venting system from lower basement levels shall also be provided. The system shall be of such design as to operate on actuation of heat / smoke sensitive detector or sprinklers, if installed, but shall have a considerably superior performance compared to the standard units. It shall also be an arrangement to start it manually.

Mechanical extractors shall have an internal locking arrangement, so that extractors shall continue to operate and supply fan shall stop automatically with the actuation of fire detectors. Mechanical extractors shall be designed to permit 30 air changes per hour in case of fire or distress call.

Mechanical extractors shall have an alternative source of supply.

Ventilating ducts shall be integrated with the structure and made out of brick masonry or reinforced cement concretes as far as possible and when this duct crosses the transformer area or electrical switchboard, fire dampers shall be provided.


Use of basements for kitchens working on gas fuel shall not be permitted, unless air conditioned. If cut outs are provided from basements to the upper floors or to the atmospheres, all sides cut out openings in the basements shall be protected by sprinkler head at close spacing so as to form a water curtain in the event of a fire.




(1)	(2)	(3)
7. Escape route.	Not indicated	Direction in which the inmates should have to move in the event of any emergency have to be indicated in the corridor/passage on each floor as a guide during evacuation. These marking should be in luminous paint.

D. The builder should arrange for the following fire fighting and evacuation measures:-

Details (1)	Existing (2)	Recommendation (3)
1. Electric power supply.	---	Circuits for water pumps, lifts, staircase lighting in the building should be by separate line and independently connected so that they can be operated by one switch installed the ground floor. Dual operated switches should be installed in the service room for terminating the standby supply. As proposed 3 standby generators, 2 each of 1,000 KVA capacity & another of 750 KVA capacity shall be installed at ground floor to supply alternative power for staircase lighting, corridor lighting, fire fighting systems, lifts etc., in the event of failure of electricity supply, in the building
2. Wet riser-cum-down comer.	Proposed to provide 4 Wet riser-cum-down comer systems.	As proposed 4 Wet Riser-cum-down comer systems, near the staircases shall be provided. Each riser should be of 150 mm internal diameter and of G.I. 'C' class pipe. From each riser double hydrant outlets should be provided at each landing. Hose reel hose of minimum 19 mm size of adequate length to reach the farthest point of each floor should be provided with a shut off branch having a nozzle of 5 mm size. The hose reel hose should be connected at each landing by means of an adaptor. A minimum of 2 external hydrants at a suitable locations (adjacent to the compound wall) with adequate space between them should also be provided from the each system. Adequate B.I.S. marked reinforced rubber



(1)	(2)	(3)
		lined delivery hoses of 63 mm size to reach the farthest point of the floor/setbacks from the system should be provided with a branch pipe near each hydrant outlet in a proper box to protect it from withering. At least two fire service inlets to boost the water in the riser directly from the mobile pump should also be provided. These inlets should be located at an easily accessible position, preferably near the entry point to the premises. Each wet riser-cum-down comer system of should be connected to an overhead tank of 25,000 litres capacity and an underground tank of 1,00,000 litres capacity. One diesel driven pump and one electrically driven pump, each capable of delivering 2280 litres of water per minute at 0.3N/mm2 pressure and an jockey pump with a capacity of 180 LPM shall be installed near the combined underground tank. The impeller of all the pumps should be made of bronze.
3. Manually operated fire alarm system	Proposed to provide manually operated electrical fire alarm system with call boxes near each staircase landing.	Manually operated electrical fire alarm system should be installed with call boxes located near each staircase landing of the Building. The call boxes should be of "break glass" type, where the call is transmitted automatically to the control room when the glass of the system is broken. This system should also be connected to an alternative source of power supply (diesel generator). The call boxes should be so installed that their location can be easily noticed from either direction and should be at a height of one meter from the floor level.



(1)	(2)	(3)
-----	-----	-----

4. Automatic fire detection system.

Proposed to provide automatic fire detection System is as follows:

As proposed automatic smoke detection system shall be provided with its console at ground floor level.


Floor	Smoke detector heads	Heat detector heads
Basement – 4	05	-
Basement – 3	05	-
Basement – 2	05	04
Basement – 1	12	-
Ground floor	64	10
1 st floor	52	10
2 nd floor to 30 th floor	52 on each floor	10 on each floor
31 st floor	29	-

5. Automatic sprinkler system.

Proposed to provide automatic sprinkler system is as follows:-

Adequate. Separate water and pump for sprinkler system to use 10% of the sprinkler system for about 30 minutes shall be provided.


Floor	Sprinkler Heads
Basement – 4	816
Basement – 3	742
Basement – 2	746
Basement – 1	754
Ground floor	251
1 st floor	112
3 rd , 5 th , 7 th , 9 th , 11 th , 13 th , 15 th , 17 th , 19 th , 21 st , 23 rd , 25 th , 27 th & 29 th floor	113 on each floor
2 nd , 4 th , 6 th , 8 th , 12 th , 14 th , 16 th , 18 th , 20 th , 22 nd , 24 th , 26 th , 28 th & 30 th floor	119 on each floor
31 st floor	140



(1)	(2)	(3)
6. Public address system.	Proposed to provide public address system with two way communication facility.	As proposed a public address system with two way communication facility should be provided at each floor near each staircase landing with its console at the control room, located on the ground floor.
7. Assembly Area	Not marked.	An area at an appropriate place in the allowed/ required setbacks shall be earmarked with a proper board as 'ASSEMBLY AREA' for the occupants to assemble after evacuation during practice drill and in an emergency.
8. Portable fire extinguishers.	Proposed to provide suitable type of portable fire extinguishers as per the requirements.	a) One ABC Powder extinguisher of 6 kgs. capacity for every 8 Cars at each Basement parking area. b) One ABC extinguisher of 2 kgs. capacity Should be provided near the entrance to each main switch board room, inside each lift machine room and inside each kitchen. c) One ABC Powder extinguisher of 6 kgs. capacity should be provided near the transformer, if installed and near the entrance to the D. G. Room. d) One ABC Powder extinguisher of 6 Kgs. capacity should be kept near each staircase landing on every floor. e) All the extinguishers suggested above should be with B.I.S. markings and should be located at an easily accessible position without obstructing the normal passage.




(1)	(2)	(3)
9. Fire safety plan.	---	A Fire safety plan for preventing and extinguishing any accidental fire in the building and action to be taken by the occupants in case of such fire should be prepared in advance and got approved by the Director, Karnataka Fire & Emergency Services. The fire safety plan, so approved, should contain the telephone numbers of the nearest Fire Control i.e., 101, 22971500, 22971550 and 22971600. The plan should be distributed to all the occupants and employees in the building and should be displayed on every floor. A Fire Command Station should be established in the lobby of the building on the entrance floor and such command station should be adequately illuminated. The main control of the public address system and fire alarm system should be at the Fire Command Station. A Fire Safety Director should be nominated for the building. He should conduct fire and evacuation drills periodically. He should nominate a Fire Warden for each floor and ensure that no individual of the building does anything which causes or stimulates an accidental fire and in case of lapses in respect of fire prevention measures, he should take action as deemed fit to ensure the safety from the fire point of view. If the action is beyond his capacity he should inform the Fire & Emergency Services department.
10. Training	Not indicated	40% of the occupant/employees should be got trained in fire prevention & fire fighting at the R.A.Mundkur Fire & Emergency Services Academy Bannerghatta Road, Bangalore - 560 029 within 6 months from the date of occupation of the building. For this purpose, before approaching this department for final




(1)	(2)	(3)
		clearance certificate, the applicant should give an undertaking in the form of an affidavit regarding the maintenance of the fire prevention and fire fighting measures suggested above and arranging training of 40% of the occupants in fire prevention and fire fighting within 6 months from the date of issue of the clearance certificate.
11. Helipad	Proposed to provide one Helipad on the terrace of the Building.	As proposed one Helipad on the terrace of the Building shall be provided with all fire prevention and fire fighting measures as per the specifications.

E. General:-

- 1) All the fire prevention, fire fighting and evacuation measures suggested / recommended in B, C & D shall be strictly adhered to adopted.
- 2) Hazardous materials such as petroleum products, explosives, chemicals etc. should not be stored on any floor of the building.
- 3) Refuse dumps or storage should not be permitted in any of the floors.
- 4) Liquefied petroleum gas should not be stored in the building, except limited quantity required for each kitchen.
- 5) Plan & occupancy should not be changed without informing the Fire & Emergency Services and without taking clearance.
- 6) The occupancy certificates should not be issued without obtaining the clearance certificate from the Fire & Emergency Services department as per Chapter 3.16 (v) of the Zoning Regulation 2007 of the Bangalore Development Authority.
- 7) Such reasonable changes/modifications as may be found necessary, after the building is fully constructed, will have to be agreed to be done by the builder/occupants of the building.
- 8) All the metal fittings of wet riser system and all the extinguishers suggested above should have B.I.S markings.



Subject to the strict adherence to the conditions laid down as above, issue of license for the construction of High Rise Residential Building i.e. Tower-2 at Property No. 1D No. 14-1-1, No.1, Industrial Suburb, Ward No. 14, Nagapura, Opp. Vivekananda College, Dr. Rajkumar Road, Bangalore- 560 010 may please be considered. The NOC, issued on 25-08-2011, shall be treated as cancelled.



Yours faithfully,


Director General of Police
and Director General,
Karnataka Fire & Emergency Services.

Copy to:

1) The Authorized Signatory, M/s. Palladium Constructions Pvt. Ltd., M/s. Palladium Spaces Pvt. Ltd., No.1, Dr. Rajkumar Road, Opp. Sheraton Hotel, Rajajinagar, Bangalore-560 010.

2) The Chief Fire Officer, Bangalore West Zone, Bangalore.