

DETAILS OF NOC'S/ CLEARANCES SECURED FOR PHASE - I

Agency	Description	Approval Details	Date of Aproval
Bharat Sanchar Nigam Ltd. (BSNL)	Clearance for Manawave	No. DE(S)/S-6/40/2007-08/25	19/10/07
Bangalore Water Supply and Sewerage Board (BWSSB)	NOC for Water and Sewerage Connection	No. SWSS/CE(M)/XOE(M)-II /TA-5572/2/2007-08	02/01/08
Bangalore Electric Supply Company (BESCOM)	NOC for Power Supply	SE(S)/CE(M)/EEE(C)/AE/572-74	4/05/13
Indian Air Force (IAF)	Height Clearance of 68 metres	No. Air HQ/S17726/4/ ATS/PO-CC(L)/X/40/7/05-D(Air-II)	05/02/08
Karnataka State Pollution Control Board (KSPCB)	CFE as per pollution control norms	No. PCB/107/CNP/08H-328	13/06/08
Airport Authority of india (AAI)	Height Clearance of 68 metres	No. AAI/BGI/ADI/DCO-3/ 2007/708-36	08/02/11
State Level Environment Impact Assessment Authority, Karnataka	Environmental Clearace	SEIAA 99CON:2007	03/10/08
Fire Force and Emergency Services	Fire Safety Clearance for High Rise Buildings	SB(1) 30/2012	13/08/2013

AREA STATEMENT (In SQM)				
NET SITE AREA = 39.559 ACRES			160,617.08	Sqm
	%	PERMISSIBLE (IN SQMT)	%	PROPOSED (IN SQMT)
PARKS & OPEN SPACES AREA	10%	16061.7	10.03%	16067.55
SURFACE PARKING AREA	5%	8030.85	5%	8067.85
	15%		15.03%	

NET SITE AREA AVAILABLE FOR DEVELOPMENT = 160617.00-16061.70=	144,555.30	SQMTS
PERMISSIBLE FAR AREA = 144,555.30 X 3.25 =	469,804.72	SQMTS
NET FAR AREA ACHIEVED =	195,992.28	SQMTS
TOTAL FAR (AEA = NET FAR AREA = / NET SITE AREA	195,992.28 / 144,555.30	1.36 SQMTS
TOTAL FAR ACHIEVED = 1.36<3.25		

GROUND COVERAGE AREA FOR COMMERCIAL DEVELOPMENT			
NET SITE AREA AVAILABLE FOR DEVELOPMENT =	144555.3		SQMTS
PERMISSIBLE GROUND COVERAGE = 45 %			
NET GROUND COVERAGE AREA ACHIEVED =	20392.27		SQMTS
TOTAL COVERAGE AREA= NET GROUND COVERAGE / NET SITE AREA	20,392.27 / 144,555.30	X 100	14.11%
TOTAL GROUND COVERAGE = 14.11 <45%			
CAR PARK REQUIRED = 3919.85 CARS	CAR PARKS PROVIDED = 3956 CARS		

PARKING REQUIREMENTS FOR BUILDING 1, 2, 3	
NET FAR AREA OF PROPOSED DEVELOPMENT =	195,992.28 SQMTS
PARKING REQUIRED @ 1 CAR PARK FOR EVERY 50 SQMTS OF FAR AREA = 195992.2850 = 3919.85	3,920 CARS
TOTAL NO OF CAR PARKS REQUIRED =	3920 CAR PARKS

TOTAL NO OF CAR PARKS PROVIDED IN PROPOSED DEVELOPMENT	
PARKING PROVIDED IN THE BASEMENT OF BUILDING 1	1330 CARS
PARKING PROVIDED IN THE BASEMENT OF BUILDING 1, 2 & 3 = 950 CARS	
PARKING PROVIDED IN 2ND BASEMENT OF BUILDING 1, 2 & 3 = 810 CARS	
PARKING PROVIDED IN 3RD BASEMENT OF BUILDING 1, 2 & 3 = 860 CARS	
PARKING PROVIDED IN STILT - 1 OF MLCP	= 213 CARS
PARKING PROVIDED IN STILT - 2 OF MLCP	= 213 CARS
PARKING PROVIDED IN GROUND FLOOR OF MLCP	= 90 CARS
PARKING PROVIDED IN TYPICAL 1ST - 9TH FLOOR OF MLCP = 110 CARS	
SURFACE PARKING	= 25 CARS
TOTAL NO OF CAR PARKS PROVIDED	3956 CAR PARKS

PARKS & OPEN SPACES & PARKING AREAS			
10% PARKS/OPEN SPACES		5 % PARKING	
DESC	AREA IN SQMT	DESC	AREA IN SQMT
PARK & OS-1	1609.37	PARKING-1	946.35
PARK & OS-2	3665.02	PARKING-2	4270.97
PARK & OS-3	1585.34	PARKING-3	2830.63
PARK & OS-4	1435.22		
TOTAL	10295.95	TOTAL	8047.95

MODIFIED AREA SUMMARY FOR BUILDING -2 (ALL AREAS IN SQM)								
SL.NO.	FLOOR DETAILS	GROSS AREA	BUILT UP AREA DEDUCTIONS	TOTAL BUILT-UP AREA	LIFTS DEDUCTIONS	NON FAR AREA	TOTAL NON FAR DEDUCTIONS	NET FAR AREA
			DUCTS					
1	3rd Basement floor	12740.00	1740.29	10999.71	47.61	1066.68	1067.07	9932.64
2	2nd Basement floor	13407.31	1282.4	12124.91	47.61	1163.42	1211.03	10913.88
3	1st Basement floor	10539.67	1282.4	9257.27	47.61	1163.42	1211.03	8046.24
4	Ground floor	5072.61	69.17	5003.44	47.61	1.00	2115.37	2887.76
5	First floor	5214.13	445.53	4768.59	47.61	1.00	87.61	4681.98
6	Second Floor	5083.40	399.04	4684.36	47.61	1.00	87.61	4596.75
7	Third floor	5083.40	399.04	4684.36	47.61	1.00	87.61	4596.75
8	Fourth floor	5083.40	399.04	4684.36	47.61	1.00	87.61	4596.75
9	Fifth floor	5083.40	399.04	4684.36	47.61	1.00	87.61	4596.75
10	Sixth floor	5083.40	399.04	4684.36	47.61	1.00	87.61	4596.75
11	Seventh floor	5027.49	399.04	4628.45	47.61	1.00	87.61	4540.83
12	Eighth floor	5083.40	399.04	4684.36	47.61	1.00	87.61	4596.75
13	Ninth floor	5083.40	399.04	4684.36	47.61	1.00	87.61	4596.75
14	Tenth floor	5027.49	399.04	4628.45	47.61	1.00	87.61	4540.83
15	Terrace floor	520.35	0.0	520.35	0.00	0.00	0.00	520.35
	Total	97832.23	174129	92780.04	1223.54	30367.53	31592.07	61188.17

AREA SUMMARY FOR BUILDING -1 (ALL AREAS IN SQM) (APPROVED)								
SL.NO.	FLOOR DETAILS	GROSS AREA	BUILT UP AREA DEDUCTIONS	TOTAL BUILT-UP AREA	LIFTS DEDUCTIONS	NON FAR AREA	TOTAL NON FAR DEDUCTIONS	NET FAR AREA
			DUCTS					
1	Ground floor	6963.14	64.56	6917.58	48	0.00	48.00	6789.58
2	First floor	6963.14	64.56	6917.58	48	0.00	48.00	6789.58
3	Second Floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
4	Third floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
5	Fourth floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
6	Fifth floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
7	Sixth floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
8	Seventh floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
9	Eighth floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
10	Ninth floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
11	Tenth floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
12	Eleventh floor	6963.01	64.56	6916.45	48	0.00	48.00	6789.45
13	Terrace floor	104.06	0.00	104.06	0.00	0.00	0.00	104.06
	Total	71138.34	1081.72	70568.62	576.00	324.00	900.00	69768.62

AREA SUMMARY - MLCP-01 ALL AREAS IN SQM (APPROVED)				
SL.NO.	FLOOR DETAILS	GROSS AREA	DEDUCTIONS	TOTAL BUILT UP AREA
1	2nd Basement floor	3540.62	1815.22	1834.31
2	1st Basement floor	3451.62	1713.44	3547.31
3	Ground floor	3451.62	52.30	3399.19
4	First floor	3451.62	52.30	3399.19
5	Second Floor	3451.62	52.30	3399.19
6	Third floor	3451.62	52.30	3399.19
7	Fourth floor	3451.62	52.30	3399.19
8	Fifth floor	3451.62	52.30	3399.19
9	Sixth floor	3451.62	52.30	3399.19
10	Seventh floor	3451.62	52.30	3399.19
11	Eighth floor	3451.62	52.30	3399.19
12	Ninth floor	3451.62	52.30	3399.19
13	Terrace floor	85.0	0.00	85.00
	Total	41622.78	2317.44	39964.18

AREA SUMMARY FOR BUILDING -3 (ALL AREAS IN SQM) (APPROVED)								
SL.NO.	FLOOR DETAILS	GROSS AREA	BUILT UP AREA DEDUCTIONS	TOTAL BUILT-UP AREA	LIFTS DEDUCTIONS	NON FAR AREA	TOTAL NON FAR DEDUCTIONS	NET FAR AREA
			DUCTS					
1	3rd Basement floor	12928.79	4.18	12924.61	100.16	12765.12	12865.28	59.33
2	2nd Basement floor	11060.92	4.18	10944.34	100.16	10980.81	10980.81	627.47
3	1st Basement floor	11060.92	4.18	10944.34	100.16	10980.81	10980.81	627.47
4	Ground floor	6378.79	40.71	6393.02	100.16	0.00	100.16	6292.92
5	First floor	6492.72	426.16	6066.72	100.16	0.00	100.16	5966.62
6	Second Floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
7	Third floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
8	Fourth floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
9	Fifth floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
10	Sixth floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
11	Seventh floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
12	Eighth floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
13	Ninth floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
14	Tenth floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
15	Eleventh floor	6192.96	417.83	5775.13	100.16	0.00	100.16	5674.97
16	Terrace floor	592.25	0.00	592.25	100.16	448.16	548.32	43.93
	Total	131483.22	4481.76	5601.44	1601.52	32910.40	34130.09	62119.37

TOTAL BUILT UP AREA INCLUDING MLCP = 3,42,937.29 SQM

INDEX
D- Existing Area
A- Approved Area

Note:
1. This plan is approved subject to condition as mentioned in the covering letter No. KIADB/DO-II/ /

This plan is approved subject to condition that any existing storm water drain, Natural Valley etc shall not be disturbed or closed.

Received an amount of Rs. ..... vide Receipt No. ..... towards LABOUR WELFARE CESS

Received an amount of Rs. 4,87,666.00 vide Receipt No. 108164 dt. 19.11.14 towards BUILDING PLAN APPROVAL FEE.

IADB/DO/Sanctioned/Karnataka
The Karnataka Industrial Areas
DEVELOPMENT BOARD
BANGALORE - 560 001
LICENCE IS GRANTED AS PER PLAN
VALID UPTO.... 17.04.2016.....
Date: 18.04.2014
Development Officer
& Executive Engineer - II

SITE AREA = 1,60,617.00 SQM
FAR AREA ACHIEVED = 195992.28 SQM
FAR ACHIEVED = 1.360%
GROUND COVERAGE AREA ACHIEVED=20392.27 SQM
GROUND COVERAGE ACHIEVED = 14.11%
TOTAL NO OF BUILDINGS = 4 (3 OFFICE +1 MLCP)
CAR PARK PROVIDED = 3956 NOS

KEY PLAN
NOT TO SCALE

SANCTION DRAWING

NOTE :
ALL DIMENSIONS ARE IN MILLIMETERS

ORIENTATION : N
SHEET NO : 1 OF 12

OWNERS SIGNATURE :
For GULF OIL CORPORATION LTD.
R.THIRUMANAN
Skyline Connect Housing
Nitrogen Energy Ventures Ltd
BPCA Holder for Gulf Oil Corporation Ltd
Authorised Signatory

ENGINEER'S SIGNATURE
RAJESH KUMAR. N
BCC/BL/3.1/E/3378/09-10

PROJECT TITLE :
MODIFIED SANCTION PLAN FOR BLOCK-2 FOR THE PROPOSED SOFTWARE TECHPARK / IGBU / MLCP BLOCK AT SITE SURVEY. O. SY NO.155/150,154,165/166 AND 161 OF KATHIGENAHALLI VILLAGE, JALA HOBLI, BANGALORE NORTH TALUK.

PROJECT CONSULTANTS :
RSP Design Consultants (India) Pvt Ltd
RSP
RSP House, 20 Museum Road, Bangalore - 560 025. Tel: 25580000 Fax: 25580019

SIGNATURES :

PROJECT HEAD :	PROJECT CO-ORDINATOR
Rajan	Ramprasad

SUBJECT OF DRAWING :
SITE PLAN

FILENAME : 07117_V0- STATUTORY DRGS 04.15 DWR	
SCALE : 1:1000	DATE : 27-05-2014
DRAWN : Shubhangi	CHECKED : RamPrasad
JOB NO : 4.75.0	DRAWING NO : SD -101