

Residential Development
Building - 3 & Building - 4

As per Development plan Approved.. Site Area	=	47,498.56 Sqm. (11 A. 29.56 G)
Kharab Area	=	717.20 Sqm. (7 G)
Total Site Area	=	46,782.36 Sqm. (11 A. 22.99 G)
Deduct Road Widening Area	=	778.00 Sqm.
Net Site Area Considered for Development	=	46,004.36 Sqm.
Site Area Considered for Residential Development = 7 Acres. 12.40 Guntas = 29,574.36 Sqm.		
Net Site Area for Residential Development - II	=	29,574.36 Sqm. (7 A. 12.40 G)
Area of Nala (Station DY as per actuals) - E1	=	1,168.42 Sqm.
Park & Open spaces @ 10% of E - Required	=	2957.44 Sqm.
Park & Open spaces Provided - H = 10.76%	=	3182.53 Sqm.
Civic Amenities space @ 5% of E	=	1478.72 Sqm.
Civic Amenities space Provided - J = 5.01%	=	1482.00 Sqm.
Nal Site Area for FAR = E - J	=	26,092.36 Sqm.

AREA STATEMENT BUILDING - 03

FLOORS	BUA	DEDUCT	NET	UNITS
GROUND FLOOR	4,941.23	51.36	4,895.87	7
FIRST FLOOR	4,489.04	51.36	4,417.68	14
SECOND FLOOR	4,687.92	51.36	4,636.56	14
THIRD FLOOR	3,532.40	51.36	3,481.04	14
FOURTH FLOOR	3,532.40	51.36	3,481.04	14
FIFTH FLOOR	3,532.40	51.36	3,481.04	14
SIXTH FLOOR	3,532.40	51.36	3,481.04	14
SEVENTH FLOOR	3,532.40	51.36	3,481.04	14
EIGHTH FLOOR	3,532.40	51.36	3,481.04	14
NINTH FLOOR	3,532.40	51.36	3,481.04	14
TENTH FLOOR	3,532.40	51.36	3,481.04	14
ELEVENTH FLOOR	3,532.40	51.36	3,481.04	14
TWELVETH FLOOR	3,532.40	51.36	3,481.04	14
THIRTEENTH FLOOR	3,532.40	51.36	3,481.04	14
FOURTEENTH FLOOR	3,532.40	51.36	3,481.04	14
FIFTEENTH FLOOR	3,532.40	51.36	3,481.04	14
SIXTEENTH FLOOR	3,532.40	51.36	3,481.04	14
SEVENTEENTH FLOOR	3,532.40	51.36	3,481.04	14
EIGHTEENTH FLOOR	3,532.40	51.36	3,481.04	14
NINTEENTH FLOOR	3,532.40	51.36	3,481.04	14
TWENTYETH FLOOR	3,532.40	51.36	3,481.04	14
TWENTYFIRST FLOOR	2,136.82	51.36	2,085.46	7
TERRACE FLOOR	256.89	256.89	-	-
TOTAL	79,202.86	1,425.61	77,776.85	385

AREA STATEMENT BUILDING - 04

FLOORS	BUA	DEDUCT	NET	UNITS
GROUND FLOOR	1,345.20	22.42	1,322.86	4
FIRST FLOOR	1,367.74	22.42	1,345.32	4
SECOND FLOOR	1[illegible]	22.42	1,360.97	3
THIRD FLOOR	723.40	11.21	712.19	3
FOURTH FLOOR	723.40	11.21	712.19	3
FIFTH FLOOR	723.40	11.21	712.19	3
SIXTH FLOOR	723.40	11.21	712.19	3
SEVENTH FLOOR	723.40	11.21	712.19	3
EIGHTH FLOOR	723.40	11.21	712.19	3
NINTH FLOOR	723.40	11.21	712.19	3
TENTH FLOOR	723.40	11.21	712.19	3
ELEVENTH FLOOR	723.40	11.21	712.19	3
TERRACE FLOOR	171.98	171.98	-	-
TOTAL	10,950.55	360.91	10,160.58	39

COMBINED BLOCK AREA STATEMENT

FLOORS	BUA	DEDUCT	NET	UNITS
2nd BASEMENT FLOOR	10,466.99	19,147.61	1,318.28	-
1st BASEMENT FLOOR	18,526.22	18,181.83	166.70	-
GROUND FLOOR	6,288.22	73.78	6,210.40	11
FIRST FLOOR	5,806.74	73.78	5,733.00	18
SECOND FLOOR	5,790.31	73.78	5,716.53	17
THIRD FLOOR	4,289.80	62.67	4,153.22	16
FOURTH FLOOR	4,356.80	62.67	4,193.23	16
FIFTH FLOOR	4,356.80	62.67	4,193.23	16
SIXTH FLOOR	4,356.80	62.67	4,193.23	16
SEVENTH FLOOR	4,356.80	62.67	4,193.23	16
EIGHTH FLOOR	4,356.80	62.67	4,193.23	16
NINTH FLOOR	4,356.80	62.67	4,193.23	16
TENTH FLOOR	4,356.80	62.67	4,193.23	16
ELEVENTH FLOOR	4,356.80	62.67	4,193.23	16
TWELVETH FLOOR	3,532.40	51.36	3,481.04	14
THIRTEENTH FLOOR	3,532.40	51.36	3,481.04	14
FOURTEENTH FLOOR	3,532.40	51.36	3,481.04	14
FIFTEENTH FLOOR	3,532.40	51.36	3,481.04	14
SIXTEENTH FLOOR	3,532.40	51.36	3,481.04	14
SEVENTEENTH FLOOR	3,532.40	51.36	3,481.04	14
EIGHTEENTH FLOOR	3,532.40	51.36	3,481.04	14
NINTEENTH FLOOR	3,532.40	51.36	3,481.04	14
TWENTYETH FLOOR	2,830.86	51.36	2,779.50	10
TWENTYFIRST FLOOR	2,136.82	51.36	2,085.46	7
TERRACE FLOOR	567.73	567.73	-	-
TOTAL	138,097.37	58,094.99	80,002.41	314

COVERAGE = 6,296.23 x 100 = 22.15% < 60.00%
28,384.96

FAR = 80,002.41 = 3.204 < 3.25
28,092.36

PARKING
Total Nos. of Residential Units from GF to 21st Floor in All Blocks = 314 Nos.
Nos. of Units over 50 sqm, less than 225 sqm = 254 nos.
@ 1 car / 1 unit, Cars Required = 254 x 1 = 254 cars
Nos. of Units over 225 sqm, less than 300 sqm = 51 nos.
@ 2 cars / 1 unit, Cars Required = 51 x 2 = 102 cars
Nos. of Units over 300 sqm, less than 375 sqm = 29 nos.
@ 3 cars / 1 unit, Cars Required = 29 x 3 = 87 cars
Total Cars Required = 254 + 102 + 87 = 423 Cars
10% Visitors Parking = 432 / 10 = 43.20 say 43 cars

GF to 9F Club House Area
GF = 2,866.90 Sqm.
FF = 1,016.81 Sqm.
SF = 1,156.64 Sqm.
Total = 5,124.60 Sqm.
@ 1 car /80 Sqm. Cars Required = 5128.65 = 102.57 say 103 cars
50
Total Cars Required = 423 + 43 + 103 = 569 Cars
Total Cars Provided
Second Basement floor = 348 Cars
First Basement floor = 364 Cars
Total = 712 Cars

Plan Sanction Conditions
(BBMP/Addl.Dir/JD North/EAST/2013-14)

Conditions:

1. Sanction is accorded for the proposed Residential Apartment Building.
   a) Consisting of 2 BF+GF+ 21 UP (Twenty one upper floors) only.
2. Sanction is accorded for Residential use only. The use of the building shall not be Analysed to any other use.
3. 2 Basement floors reserved for car parking shall not be converted for any other purpose.
4. Development charges towards increasing the capacity of water supply, sanitary and power mains has to be paid to BWSSB and BESCOM as the case may be.
5. Necessary shafts for running telephone cables, cabinets at ground level for postal services & space for depositing garbage within the premises shall be provided.
6. The applicant shall construct temporary toilets for the use of construction workers and that toilets be demolished after the construction.
7. The applicant shall ENSURE all workmen employed in the construction work against any accident / unforeseen incidents arising during the time of construction.
8. The applicant shall not store any building materials / debris on footpath or on roads or on drains. The debris shall be removed and transported to Area by dumping yard.
9. The applicant / builder is prohibited from putting the setback area / open spaces and the common facility areas, which shall be accessible to all the tenants and occupants.
10. The applicant shall provide a space for locating the distribution transformers & associated equipment as per K.E.R.C. (Sp & D) code having 3.00 mts. from the building within the premises.
11. The applicant shall provide a separate room (preferably 4.50 x 3.60 m in the basement) for installation of telecom equipment and also to make provisions for telecom services as per Bye-law No. 35.
12. The applicant shall maintain during construction such barricading as considered necessary to prevent dust, debris & other materials endangering the safety of people / the public and of adjacent property.
13. The applicant shall plant at least two trees in the premises.
14. Permission shall be obtained from forest department for cutting trees before the commencement of the work.
15. Licence & approved plans shall be posted in a conspicuous place of the licensed premises. The building Bye-laws and the copies of sanctioned plans with specifications shall be displayed on a frame and displayed and they shall be made available during inspections.
16. If any owner / builder contravenes the provisions of Building Bye-laws and rules in force, the Architect / Engineer / Supervisor will be debarred by the Authority in the first instance, debarred in the second instance and cancel the registration if the same is repeated for the third time.
17. Technical personnel, applicant or owner as the case may be shall strictly adhere to the duties and responsibilities specified in Schedule – IV (Bye-law No. 3.8) under sub section 9 (vi) to (x).
18. The building shall be constructed under the supervision of a registered structural engineer.
19. On completion of foundation or footings before erection of walls on the foundations and in the case of columned structure before erecting the columns "COMMENCEMENT CERTIFICATE" shall be obtained.
20. Construction or reconstruction of the building should be completed before the expiry of two years from the date of issue of license & within one month after its completion, shall apply for permission to occupy the building.
21. The building should not be occupied without obtaining "OCCUPANCY CERTIFICATE" from the competent authority.
22. Drinking water supplied by BWSSB should not be used for the construction activity of the building.
23. The applicant shall ensure that the Rain Water Harvesting Structures are provided & maintained in good repair for storage of water for non-potable purposes or recharge of ground water at all times having a minimum total capacity mentioned in the Bye-law No.
24. The building shall be designed and constructed adopting the norms prescribed by National Building Code and in the "Criteria for earthquake resistant design of structures" bearing No. IS 1893:2002 published by the Bureau of Indian Standards making the building resistant to earthquake.
25. The applicant should provide water supply meters as per Table 19 of Bye law No. 29 for the building.
26. Facilities for physically handicapped persons prescribed in schedule XI (Bye laws 31) of Building Bye-laws 2003 shall be ensured.
27. The applicant shall provide at least one connection toilet in the ground floor for the use of the visitors / servants / drivers and security shall and also entrance shall be approached through a ramp by the Physically Handicapped persons together with the wheelchair inside.
28. The Occupancy Certificate will be considered only after ensuring that the provisions of conditions vide 03, 04, 25 & 26 are provided in the building.
29. The applicant shall ensure that no inconvenience is caused to the neighbours in the vicinity of construction and that the construction activities shall also be done between 10.00 PM to avoid inconvenience during late hours.
30. Garbage originating from Apartments / Commercial buildings shall be segregated into organic and inorganic waste and should be processed in the **Recycling processing unit** (U.I.) capacity installed at site for its re-use / disposal (Applicable to Residential units of 50 and above and 3000 Sqm and above built up area for Commercial buildings).
31. The structures with basements shall be designed for structural stability and safety to ensure for soil stabilization during the course of excavation for basements with safe design for retaining walls and super structure for the safety of the structure as well as neighbouring property, public roads and footpaths, and besides ensuring safety of workmen and general public by erecting safe barricades.
32. The NOC from KSPCB / State Level Environment Impact Assessment Committee (SEIAC) / The Ministry of Environmental and Forest (MOEF) should be taken before commencement of work (if applicable).
33. Sufficient two-wheeler parking shall be provided as per requirement.
34. Traffic Management Plan shall be obtained from Traffic Management Consultant for all high rise structures which shall be got approved from the Competent Authority if necessary.
35. The owner / association of high rise building shall obtain occupancy certificate from Fire Force Department every two years with due intimation to the department regarding working condition of Fire Safety Measures installed. The certificate should be produced to the corporation and other parties as per the provisions in the act and rules.
36. The Owner / Association of the high rise building shall get the building inspected by empanelled agencies of the Fire Force Department to ensure that the fire equipments / alarm are in good and workable condition, and an affidavit to that effect shall be submitted to the corporation and Fire Force Department every two.
37. The owner / Association of high rise building shall obtain clearance certificate from the Electrical Inspectorate every two years with due intimation to the department regarding working condition of electrical installations / Lifts etc. The certificate should be produced to the corporation and other parties as per the relevant provisions in the act / Rules.
38. The Owner / Association of the high rise building shall conduct two mock – drills in the building, one before the onset of summer and another during the summer and ensure adequate safety as required by the Fire Force.
39. Payment of scrutiny fees for sanction of this plan is subject as result of W.P.No. 40962/2008 & 22913/2012.
40. Appropriate Charges for the property should be paid as decided by the BBMP in future.
41. Permission has to be obtained from Chief Engineer (Storm Water Drain) to construct Cross Over Bridge across the Nala as per Documented Plan before Commencement of work.
42. The Applicant / Developers shall constructed the Cross Over Bridge across the Nala as per the approved Development at their own cost and the design of the Cross Over Bridge should be approved by Chief Engineer (Storm Water Drain).
43. The NOC from SEIAA and Central Flying Training School should be submitted before obtaining Commencement Certificate.
44. In case of any false information, misrepresentation of facts, or pending court cases, the plan sanction is deemed cancelled.

Special Condition as per Labour Department of Government of Karnataka vide ADDENDUM (Hosakkaga Hoodisu) Letter No. LD/95/LET/2013, dated: 01.04.2013

1. Registration of Applicant / Builder / Owners / Contractor and the construction workers working in the construction site with the "Karnataka Building and Other Construction workers Welfare Board" should be strictly adhered to.
2. The Applicant / Builder / Owner / Contractor should submit the Registration of establishment and list of construction workers engaged at the time of issue of Commencement Certificate. A copy of the same shall also be submitted to the concerned local Engineer in order to inspect the establishment and ensure the registration of establishment and workers working in construction site or work place.
3. The Applicant / Builder / Owners / Contractor shall also inform the changes if any of the list of workers engaged by him.
4. At any point of time No Applicant / Builder / Owner / Contractor shall engage a construction worker in the site or work place who is not registered with the "Karnataka Building and Other Construction workers Welfare Board".

Note:
1. Accommodation shall be provided for setting up of schools for imparting education to the children of construction workers in the labour camps / construction sites.
2. List of children of workers shall be furnished by the Builder / contractor to the Labour Department which is mandatory.
3. Employment of child labour in the construction activities strictly prohibited.
4. Obtaining NOC from the Labour Department before commencing the construction work is a must.
5. BBMP will not be responsible for any dispute that may arise in respect of property in question.
6. In case if the documents submitted in respect of property in question is found to be false or fabricated, the plan sanctioned stands cancelled automatically and legal action will be initiated.

Sl. No.	Name of the Statutory Department	Authorised No. & Date	Conditions/Clearance
1	Fire & Emergency Department		
2	Environment Impact Assessment Authority (EIAA)		
3	Pollution Control Board		
4	Metro Rail Project		
5	Traffic Police		
6	Urban Development Department		
7	Bangalore Water Supply and Sewerage Board (BWSSB)		
8	Bangalore Electricity Supply Company Limited (BESCOM)		
9	Karnataka Power Transmission Corporation Limited (KPTCL)		
10	Karnataka Urban Water Sewerage and Drainage Board (KUWSDB)		
11	Bangalore Development Authority (BDA)		
12	Karnataka Slum Development Board		
13	Bangalore Metropolitan Land Reforms (BMLR)		
14	Karnataka Industrial Areas Development Board (KIADB)		
15	Karnataka Housing Board (KHB)		
16	Karnataka Forest Department		
17	Karnataka Urban Infrastructure Development Finance Corporation (KUIDFC)		
18	Karnataka Urban Development Authority (KUDA)		
19	Bangalore Mahanagara Palike (BMP)		
20	Bangalore Metropolitan Transport Corporation (BMTC)		
21	Karnataka Road Development Corporation Limited (KRDCL)		
22	Karnataka Urban Water Supply Project (KUWSP)		
23	Karnataka Urban Water Supply Modernization Project (KUWSMP)		
24	Karnataka Urban Water Supply and Drainage Project (KUWSDP)		
25	Karnataka Urban Water Supply Improvement Project (KUWSIP)		
26	Karnataka Urban Water Supply Project (KUWSP)		
27	Karnataka Urban Water Supply Modernization Project (KUWSMP)		
28	Karnataka Urban Water Supply and Drainage Project (KUWSDP)		
29	Karnataka Urban Water Supply Improvement Project (KUWSIP)		

The Applicant has paid the vide fee Receipt No. TP/UDTP/WST/351/2013-14/EMV/0104 Dated 29/01/2014 of the following:

1	Ground Floor	Rs.[illegible]
2	Betterment Charges	Rs.[illegible]
3	4(1)-a Building	Rs.[illegible]
4	Security Deposit	Rs.[illegible]
5	License Fees	Rs.[illegible]
6	Cauvery Charges	Rs.[illegible]
7	Computerisation Fees	Rs.[illegible]
8	1% Service Charges for Labour Cess	Rs.[illegible]
	TOTAL	Rs.2,77,72,383/-
	SAY Rs.	Rs.2,77,73,000/-
9	Labour Cess	Rs.[illegible]

ನಕಲು ಪ್ರತಿ

ನಿಮ್ಮ ಯೋಜನೆಯನ್ನು ಮುಂದಿನ ಅವಶ್ಯಕ ಅನುಮತಿ ನೀಡಲಾಗಿದೆ [illegible]
ಜೊತೆಗೆ : ಬಿ.ಬಿ.ಎಂ.ಪಿ (ಉ) (ಪ್ರ) ಬಿ.ಎ.ಸ್. ಸಂ: UD 327 LBC 2013 14
ದಿನಾಂಕ: [illegible]
ಪತ್ರದ ಒಳಪುಟ ಅನುಮತಿಯನ್ನು ದಿನಾಂಕ: [illegible]
ರಂದು ಪಾವತಿಸಿದ ಮೊತ್ತ ಮುಂದಿನ ಅವಶ್ಯಕತೆ.
(ಕಂದಾಯ ಅಧಿಕಾರಿ ಅಧಿಕೃತ ಮುದ್ರೆ)

ಅಭಿವೃದ್ಧಿ ಪರಿವೀಕ್ಷಣೆ (ಪೂರ್ವ ಮೇಲ್ವಿಚಾರಣೆ ಅಧಿಕಾರಿ)
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

BUILDING - 3 & 4



SCHEDULE OF OPENINGS

MARK	SIZE	LOCATION	DESCRIPTION
D	1050*2100	STAIRCASE	FIRE RATED DOOR
PVC	1800*2100	PVC	FIRE RATED DOOR
SD	1800*2100	LIFT LOBBY DOOR	ALUMINIUM DOOR
MD	1500*2100	CLUB, SPA, GYM	ALUMINIUM DOOR
SD	1750*2100	ENT. DOOR	PANELLED DOOR
D	1750*2100	BEDROOM	GLAZED DOOR
SD	1200*2100	TOILET	FLUSH DOOR
SD	1200*2100	MAID'S ROOM	FLUSH DOOR
SD	1200*2100	TOILET MAID'S	FLUSH DOOR
SW	1400*2100	BEDROOM	ALUMINIUM WINDOW
SW	1200*2100	BEDROOM	ALUMINIUM WINDOW
SW	1750*2100	BEDROOM	ALUMINIUM WINDOW
SW	1750*2100	BEDROOM	ALUMINIUM WINDOW
W1	4300*2100	BEDROOM	ALUMINIUM WINDOW
W2	5100*2100	BEDROOM	ALUMINIUM WINDOW
W3	3400*2100	BEDROOM	ALUMINIUM WINDOW
W4	1300*2100	BEDROOM	ALUMINIUM WINDOW
W5	1300*2100	BEDROOM	ALUMINIUM WINDOW
V	1450*2100	TOILET	VENTILATOR

OWNER'S SIGNATURE:

GPA HOLDER
CENTURY REAL ESTATE HOLDINGS PVT LTD

ARCHITECT'S SIGNATURE

JAYANT VAITHA
(IECC/SL-3.6/ A 1668/07-08)

BBMP SANCTION DRAWING

PROJECT TITLE

PROPOSED RESIDENTIAL DEVELOPMENT FOR CENTURY REAL ESTATE HOLDINGS PVT. LTD. AT BBMP KHATA NO. - 853/1/107/2,3/108/1,116/2,3 & KHATA NO. 418/106/7,8,9 & 19 & 1,4,5,6,107/1, 116/1, 117/3, 121, 118/2 ON SY NO 107/2,, 116/2, 107/3, 116/3, 108/1, 116/1, 117/3, 107/1,121 PART & 115/2 (P) OF AMRUTHAHALLI VILLAGE. SY NO. 19/6, 19/7, 18/3, 18/2, 19/1, 19/4, 19/5, 19/6 OF BYATARAYANAPURA VILLAGE. YELAHANKA HOBLI, BANGALORE NORTH TALUK

DRAWING TITLE
SITE PLAN

N

DRAWING NO:	SCALE 1:500	DATE 25.04.2013	
DRAWN PHILIP	CHECKED SHANKER		
SHEET NO. - 01			