

4. **ADDITIONAL REQUIREMENTS:**

A] FALSE CEILING (if provided) :

False ceiling if provided in the building shall be of non-combustible material. Similarly, the suspenders of the false ceiling shall be of no combustible materials.

B] MATERIALS FOR INTERIOR DECORATION/FURNISHING:

The use of materials which are combustible in nature and may spread toxic fume/gases should not be used for interior decoration/furnishing, etc.

C] EMERGENCY ESCAPE ROUTE PLAN:

Emergency exit route plan framed in glass shall be displayed in the common corridor, cross passages, staircase/lift lobbies of each floor level.

The party has already paid the Scrutiny fees of Rs.1,10,100/- vide Receipt No.-1660472 & SAP DOC. No.-1000569820 and Receipt No.-1660473 & SAP DOC. No.-1000569830, dated 07/04/2010 on the gross built-up area of 11,000.00 Sq. Mtrs. as certified by the Architect.

Further, the party has paid the additional Scrutiny fees of Rs.79,100/- vide Receipt No.-5918184 & SAP DOC. No.-1001272770, dated 12/11/2012, of Rs.19,775/- vide Receipt No.-5918183 & SAP DOC. No.-1001272767, dated 12/11/2012, of Rs.27,425/- vide Receipt No.-5918182 & SAP DOC. No.-1001272762, dated 12/11/2012, on the gross built-up area of 9455.00 Sq. Mtrs. as certified by the Architect vide his letter dated 06/11/2012.

Now, paid the Scrutiny fees of Rs.1,53,500/- vide Receipt No.-5038194 & SAP DOC. No.-1002782102, dated 14/12/2016 on the gross built-up area of 9997.00 Sq. Mtrs. as certified by the Architect

However, E.E.B.P. (City) is requested to verify and inform this office, if found to be more, for the purpose of levying additional capitation fees.

Note:

- The firefighting shall be carried out by approved licensed agency.
- There shall not be any trees obstructing fire appliances reach in compulsory open spaces, required as per DCR.
- The Area Calculation submitted by the architect in the plans shall be verified by E.E.B.P. and if any change then the proposal shall be referred back to this department.
- This NOC is issued from Fire Safety Point of view.
- The schematic drawings/plans of active fire safety measures recommended by this department in the NOC i.e. Sprinkler system, Drencher system, Smoke Detection System, Wet riser system, Public Address system etc. shall be submitted and got approved from CFO prior to installation.
- E.E.B.P. (City) requested to scrutinized the plans as per amended DCR & verify civil work and all other requirements pertaining to civil Engineering side